



BA-PHALABORWA MUNICIPALITY
MEMORANDUM
- BUDGET AND TREASURY –

TO : *Prospective Service Provider*
FROM : *SCM/STORES*
DATE : *17/09/2019*
ENQUIRIES : *STORES*
TELEPHONE : *015 780 6362/61*
REF : *135970*

Kindly furnish this office with a written quotation for supply of goods/ services as detailed below. The quotation must be submitted on the letterhead of your Business and Brought to our offices 3 Nyala Street, Phalaborwa not later than **26/09/2019 at 12HOO**

QUANTITY	Description	PRICE/UNIT (Inc .VAT)	DELIVERY PERIOD
1	Installation of fencing palisade steel fence at Traffic Department (Fleet)		
	See specification below:-		

Please number your quotes (Your Ref no)

The following conditions will apply:

- *Price (s) quoted must be valid for at least thirty (30) days from date of your offer.*
- *The municipality retains the prerogative to reject any quotes it deems to be excessive*
- *A firm delivery period must be indicated.*
- *Tax Clearance Certificate*
- *A service provide be registered with central supplier database (CSD)*
- *Registered with CIPRO (CK 1 or 2 document)*
- *BBBEE Certificate certified by a SANAS accredited institution.*
- *Completed MBD4 (Declaration of Interest) Form*

Fill in and Return the Declaration of Interest Form.



BA-PHALABORWA MUNICIPALITY

MEMORANDUM

- BUDGET AND TREASURY -

INSTALLATION OF STEEL PALISADE FENCING AT TRAFFIC DEPARTMENT(FLEET)

ITEM	DESCRIPTION	UNIT	QTY	RATE	AMOUNT
1	PRELIMINARIES & GENERAL				
	a)Site establishment Includes, transporting of materials from lulokani municipal office to site	Item	1		
2	SITE CLEARANCE & EXCAVATIONS				
	a)Remove Old diamond mesh fence	m	144		
	b)Digging of holes/ trenches for Palisade poles, with minimum depth of 400mm but not exceeding 600mm	m3	1,3		
3	INSTALLATION OF PALISADE				
	a)Cast 20Mpa concrete on excavated holes with Poles inside	m3	1,6		
	b)Install 3.0m x 2.4m palisade panel	m	144		
	b)Design and install 7m steel sliding gate similar to main office gate	Item	2		
	c) Install Pole caps on each	No	45		
4	FINISHING				
	a)1st coat of H2O Red Oxide primer apply two coats (supply materials) (2.4m high x 144m long)	m	144		
	b)2nd Coat of Brilliant Green apply two coats of Acrylic paint (Supply materials) (2.4m high x 144m long)	m	144		
	Total				



BA-PHALABORWA MUNICIPALITY
MEMORANDUM
- BUDGET AND TREASURY –