



BA-PHALABORWA MUNICIPALITY
MEMORANDUM
- BUDGET AND TREASURY –

TO : *Prospective Service Provider*
FROM : *SCM/STORES*
DATE : *17/09/2019*
ENQUIRIES : *STORES*
TELEPHONE : *015 780 6362/61*
REF : *135969*

Kindly furnish this office with a written quotation for supply of goods/ services as detailed below. The quotation must be submitted on the letterhead of your Business and Brought to our offices 3 Nyala Street, Phalaborwa not later than **26/09/2019 at 12H00**

QUANTITY	Description	PRICE/UNIT (Inc .VAT)	DELIVERY PERIOD
1	Installation of Palisade steel fencing at Lulekani Archieves		
	See specification below:-		

Please number your quotes (Your Ref no)

The following conditions will apply:

- *Price (s) quoted must be valid for at least thirty (30) days from date of your offer.*
- *The municipality retains the prerogative to reject any quotes it deems to be excessive*
- *A firm delivery period must be indicated.*
- *Tax Clearance Certificate*
- *A service provide be registered with central supplier database (CSD)*
- *Registered with CIPRO (CK 1 or 2 document)*
- *BBBEE Certificate certified by a SANAS accredited institution.*
- *Completed MBD4 (Declaration of Interest) Form*

Fill in and Return the Declaration of Interest Form.



BA-PHALABORWA MUNICIPALITY
MEMORANDUM
- BUDGET AND TREASURY -

INSTALLATION OF STEEL PALISADE FENCING AT LULEKANI ARCHIEVES

ITEM	DESCRIPTION	UNIT	QTY	RATE	AMOUNT
1	PRELIMINARIES & GENERAL				
	a) Site establishment Includes, transporting of materials from lulekani municipal office to site	Item	1		
2	SITE CLEARANCE & EXCAVATIONS				
	a) Remove trees along the perimeter of fence	m	459		
	b) Digging of holes/ trenches for Palisade poles, with minimum depth of 400mm but not exceeding 600mm	m ³	3,1		
3	INSTALLATION OF PALISADE				
	a) Cast 20Mpa concrete on excavated holes with Poles inside	m ³	2,3		
	b) Install 3.0m x 1.8m palisade panel	m	459		
	b) Design and install 7m steel sliding gate with as per clients specification	Item	2		
	c) Install Pole caps on each	No	134		
4	FINISHING				
	a) 1st coat of H2O Red Oxide primer apply two coats (supply materials) (1.8m high x 406m long)	m	459		
	b) 2nd Coat of Brilliant Green apply two coats of Acrylic paint (Supply materials) (1.8m high x 406m long)	m	459		

Total



BA-PHALABORWA MUNICIPALITY
MEMORANDUM
- BUDGET AND TREASURY –