



BA-PHALABORWA MUNICIPALITY
MEMORANDUM
- BUDGET AND TREASURY –

TO : *Prospective Service Provider*
FROM : *SCM /STORES*
DATE : *12/09/2019*
ENQUIRIES : *STORES*
TELEPHONE : *015 780 6362/61*
REF : *135959*

Kindly furnish this office with a written quotation for supply of goods/ services as detailed below. The quotation must be submitted on the letterhead of your Business and Brought to our offices 3 Nyala Street, Phalaborwa not later than **20/09/2019 at 12HOO**

QUANTITY	Description	PRICE/UNIT (Inc .VAT)	DELIVERY PERIOD
1	Repair of swimming pool		
	As per attached specification supply and install		

Please number your quotes (Your Ref no)

The following conditions will apply:

- *Price (s) quoted must be valid for at least thirty (30) days from date of your offer.*
- *The municipality retains the prerogative to reject any quotes it deems to be excessive*
- *A firm delivery period must be indicated.*
- *Tax Clearance Certificate*
- *A service provide be registered with central supplier database (CSD)*
- *Registered with CIPRO (CK 1 or 2 document)*
- *BBBEE Certificate certified by a SANAS accredited institution.*
- *Completed MBD4 (Declaration of Interest) Form*

Fill in and Return the Declaration of Interest Form.



BA-PHALABORWA MUNICIPALITY
MEMORANDUM
- BUDGET AND TREASURY -

FIBREGLASS POOL LINING AT 30 BRANDT STREET

Item	Description	unit	Qty	rate
PREP	Grind pool surface and mosaic to the correct profile Cut anchor grooves where needed Cut anchoring points throughout shell	m2	48,00	
POOL INTERIOR	Laminate & anchor with 450 CSM & Tissue, polyester resin onto current Coat lining with grey Pool Coat up to underneath coping edging	m	26,00	
MOSAIC PLASTER	Current Mosaic tile waterline does not need to be removed. We do a thorough grind for maximum bonding on this area. If loose or flaking plaster is encountered then repairs must be done first If cracks are encountered we will stitch repair with GRP Please Note: GRP Lining/Topcoat must air dry for 7 days before filling with water Due to hand lamination, visible brush streaks/joins will be visible Floor area & surface must be dry before GRP lamination can be done			

NB Proof of atleast 10 years experience with similar jobs is a prerequisite for this work


15/08/19

