

## BA-PHALABORWA MUNICIPALITY

MEMORANDUM

- BUDGET AND TREASURY \_

: Prospective Service Provider : SCM /STORES : 05/ 08/2020 : STORES : 015 780 6362/61 : 135385

Kindly furnish this office with a written quotation for supply of goods/ services as detailed below. The quotation must be submitted on the letterhead of your Business and Brought to our offices 3 Nyala Street, Phalaborwa not later than **14/08/2020 at 12HOO** 

QUANTITY	Description	PRICE/UNIT (Inc. VAT)	DELIVERY PERIOD
1	Refurbishment of Namakgale town hall ceiling		
	See the attached specification		

## Please number your quotes (Your Ref no)

The following conditions will apply:

- > Price (s) quoted must be valid for at least thirty (30) days from date of your offer. >
  - The municipality retains the prerogative to reject any quotes it deems to be excessive > A firm delivery period must be indicated.
- Tax Clearance Certificate
- A service provider be registered with central supplier database (CSD)
- > Registered with CIPRO (CK 1 or 2 document)
- > BBBEE Certificate certified by a SANAS accredited institution.
- > Completed MBD4 (Declaration of Interest) Form
- > Completed MBD6.2 Form

Fill in and Return the Declaration of Interest Form.

EM	DESCRIPTION	UNIT	QTY	RATE	AMOUNT
1	PRELIMINARIES & GENERAL				
					- Constant of the International
	a) Allowance for site estsblishement , accomodation etc	Item	1		
		A	-	1	
2	REMOVAL OF EXISITING CEILINGS	111		-	
	Remove suspended ceiling panels, grids, hangers and etc				_
_					_
	Finished floor to ceiling height		700		
	a)Exceeding 2.5m but not exceeding 3.5m	m2	765		
	Liferentia a factoria construction F. Ora		245		
	b)Exceeding 3.5m but not exceeding 5.0m	m2	315		
1	c) Carting away of removed materials to a place selected by the			-	
	client within a distance of 15km Radius	m3	24		
	Client within a distance of 15km Radius	1115	24		
	d) Remove and re-install 200mm x 150mm x 6m box gutter to fix				
	roof leak in room no 4	item	1		
		1			
3	INSTALLATION OF NEW CEILING				
	The installation of the suspended ceiling shall be strictly in				
	accordance with the latest specification. To ensure a quality				
	installation with satisfactory performance life, it is strongly				1 -
	recommended that members of the South African Building		-		
	김 전 것 같은 것 것 것 같은 것 같이 지수요? 같은 것 같은				
	Interior Systems Association (SABISA) are employed.				
	Certificates of compliance as issued by the contractor may provide				
	further proof of competency. SABISA monitors				
	its members for the use of correct installation techniques, the use				
	of quality materials, and the application of quality				
	workmanship.				
	Supply and Install Acoustic false ceiling tiles with new grids,				-
	hangers etc				
	hangers etc				
	Finished floor to ceiling height				
	a)Exceeding 2.5m but not exceeding 3.5m	m2	765		
	b)Exceeding 3.5m but not exceeding 5.0m	m2	315		
	c) Supply and install Contemporary Aluminium office lights 590 x				
	590	no	38		
	d) Supply and install XPS Polystherene cornice 79mm x 81mm				
	design	m	371		
	10% of Project value shall be deducted and be degreed as			Series Marco	
	retention for a period of six months				
	//	Q			

## REPAIR AND MAINTANANCE OF NAMAKGALE TOWN HALL ( SUSPENDED CEILING)

A 23/07/2020

Total