

# **BA-PHALABORWA MUNICIPALITY**

### **MEMORANDUM**

### - BUDGET AND TREASURY -

TO : Prospective Service Provider

FROM : SCM /STORES

DATE : 16/07/2019 ENQUIRIES : STORES

TELEPHONE : 015 780 6362/61

REF : 132993

Kindly furnish this office with a written quotation for supply of goods/ services as detailed below. The quotation must be submitted on the letterhead of your Business and Brought to our offices 3 Nyala Street, Phalaborwa not later than **24/07/2019 at 12HOO** 

QUANTITY	Description	PRICE/UNIT (Inc .VAT)	DELIVERY PERIOD
12	Supply and Installation of Alarms system with motion dectors		
	Phalaborwa stores		

# Please number your quotes (Your Ref no)

The following conditions will apply:

- Price (s) quoted must be valid for at least thirty (30) days from date of your offer.
- The municipality retains the prerogative to reject any quotes it deems to be excessive
- > A firm delivery period must be indicated.
- > Tax Clearance Certificate
- A service provide be registered with central supplier database (CSD)
- > Registered with CIPRO (CK 1 or 2 document)
- > BBBEE Certificate certified by a SANAS accredited institution.
- > Completed MBD4 (Declaration of Interest) Form

Fill in and Return the Declaration of Interest Form.



# BA-PHALABORWA MUNICIPALITY MEMORANDUM - BUDGET AND TREASURY –





## BA-PHALABORWA MUNICIPALITY OFFICE OF THE MUNICIPAL MANAGER RISK MANAGEMENT

# Specification: Supply and installation of Alarm system with Outdoor Motion Detectors

No.	Description	Quantity
1.	Alarm System	
	Upgrading of the current 8 Zone IDS Alarm system to 16 Zone	01
	(Including 02x Remote Controls) The current motion sensors installed	
	to work on the new system.	
2.	Outdoor hardwired motion detectors	
	High mount outdoor passive infrared motion detector with 90-	
	degrees detection pattern, Detection range +12m, Active IR digital	
	anti-masking, Water resistant design, LED Status light, 2 PIRs able to	
	distinguish between a pet and a human being, Masking strips, Slope	
	friendliness, horizontal and vertically adjustable bracket, wiring	
	Mounting height 2.5 – 3M, Power input 9.5 – 18V DC and Vegetation	
	sway analysis logic.	
3.	Installation Labour	