



BA-PHALABORWA MUNICIPALITY  
MEMORANDUM  
- BUDGET AND TREASURY –

**TO** : *Prospective Service Provider*  
**FROM** : **SCM /STORES**  
**DATE** : **09/01/2020**  
**ENQUIRIES** : **STORES**  
**TELEPHONE** : **015 780 6362/61**  
**REF** : **136871**

Kindly furnish this office with a written quotation for supply of goods/ services as detailed below. The quotation must be submitted on the letterhead of your Business and Brought to our offices 3 Nyala Street, Phalaborwa not later than **16/01/2020 at 12H00**

<b>QUANTITY</b>	<b>Description</b>	<b>PRICE/UNIT (Inc. VAT)</b>	<b>DELIVERY PERIOD</b>
	<b>Supply installation and commissioning of UPS inverter and batteries</b>		
	<b>Spec attached</b>		

**Please number your quotes (Your Ref no)**

**The following conditions will apply:**

- **Price (s) quoted must be valid for at least thirty (30) days from date of your offer. ➤**
- The municipality retains the prerogative to reject any quotes it deems to be excessive**
- **A firm delivery period must be indicated.**
- **Tax Clearance Certificate**
- **A service provider be registered with central supplier database (CSD)**
- **Registered with CIPRO (CK 1 or 2 document)**
- **BBBEE Certificate certified by a SANAS accredited institution.**
- **Completed MBD4 (Declaration of Interest) Form**

**Fill in and Return the Declaration of Interest Form.**

Supply, installation and commissioning of UPS inverter and batteries

QTY	DISCRIPTION
1	12.5 kVA (10 KW) Standby Silent Diesel Generator (380V) Power Output
1	Inverter/Charger for Solar/Generator and Grid Assisted Power Feeds: 12KVA Inverter and Charger 120Amp, Grid and Generator assisted UPS, Over load, Over voltage, under voltage, temperature and short circuit protected, Zero spark connection with forced cooling, Battery Level Indicator, Generator and grid input with assisted switch over selection, Generator start output relay, Keypad and LCD display with Nominal Battery Voltage: 48Vdc, Output Voltage: 220-230 Vac General Specifications: Dimensions (w x h x d): 760mm x 360mm x 460mm, Weight: 100kg
6	Front Terminal 12V 200AH battery: Output terminal of low resistance, Perfect sealing of post, multi-element alloy, Advanced case and lid heat sealing technology, Safety valve.
1	Cabinet wiring kit - 8 x 25mm soft strand Cable for Batteries, 14 x 20mm x 3mm Copper Buzz Bar, 16 x Cable Lug 10x 25mm Earth tags
1	Manual Transfer switch
50	6mm Suffix twin and Earth cable
50	10mm GP wire Red, Black and yellow/Green 12Meter
2	50A DP CBI Circuit Breaker (2 circuit)
2	25mm soft strand Cable for Batteries
1	20mm x 3mm Copper Buzz Bar
6	Cable Lug 10x 25mm Earth tags
1	Single Phase compact type 1 + 2 surge protection units with Remote fault indicator contact management
1	Installation and commissioning
1	Shipping Costs for Delivery to Client Premises