



BA-PHALABORWA MUNICIPALITY
MEMORANDUM
- BUDGET AND TREASURY -

TO : Prospective Service Provider
FROM : SCM /STORES
DATE : 19/01/2023
ENQUIRIES : STORES
TELEPHONE : 015 780 6361/62
REF : REQ2266

Kindly furnish this office with a written quotation for supply of goods/ services as detailed below. The quotation must be submitted on the letterhead of your Business and Brought to our offices 3 Nyala Street, Phalaborwa not later than 27/01/2023 at 12H00

QUANTITY	Description	PRICE/UNIT (Inc. VAT)	DELIVERY PERIOD
400m	Installation of Palisade fence for a distance of 400m at Lulekani		
	Graveyard as per attached Specification		

Please number your quotes (Your Ref no)

The following conditions will apply:

- Price (s) quoted must be valid for at least thirty (30) days from date of your offer.
- The municipality retains the prerogative to reject any quotes it deems to be excessive
- A firm delivery period must be indicated.
- Tax Clearance Certificate
- A service provider be registered with central supplier database (CSD)
- Registered with CIPRO (CK 1 or 2 document)
- BBBEE Certificate certified by a SANAS accredited institution.
- Completed MBD4 (Declaration of Interest) Form
- Completed MBD6.2 FOR
- Evaluation criteria: 80/20

Fill in and Return the Declaration of Interest Form.



BA-PHALABORWA MUNICIPALITY
MEMORANDUM
- BUDGET AND TREASURY -

STAMP OF BUREAU OF
DEVELOPMENT
NEEDED FOR
REGISTRATION
PHALABORWA

INSTALLATION OF STEEL PALISADE FENCING AT PHALABORWA GRAVEYARD

ITEM	DESCRIPTION	UNIT	QTY	RATE	AMOUNT
1	PRELIMINARIES & GENERAL				
	a) Site establishment	Item	1		
2	SITE CLEARANCE & EXCAVATIONS				
	a) Remove trees along the perimeter of fence	m	406		
	b) Digging of holes/ trenches for Palisade poles, with minimum depth of 400mm but not exceeding 600mm	m ³	2,2		
3	INSTALLATION OF PALISADE				
	a) Cast 20Mpa concrete on excavated holes with Poles inside	m ³	1,8		
	b) Install 3.0m x 1.8m palisade panel	m	406		
	b) Design and install 9m steel sliding gate with as per clients specification	Item	1		
	c) Install Pole caps on each	No	136		
4	FINISHING				
	a) 1st coat of H2O Red Oxide primer apply two coats (supply materials) (1.8m high x 406m long)	m	406		
	b) 2nd Coat of Brilliant Green apply two coats of Acrylic paint (Supply materials) (1.8m high x 406m long)	m	406		
Total					