



BA-PHALABORWA MUNICIPALITY

MEMORANDUM

BUDGET AND TREASURY

TO : *Prospective Service Provider*  
FROM : *SCM /STORES*  
DATE : *25/03/2022*  
ENQUIRIES : *STORES*  
TELEPHONE : *015 780 6361/62*  
REF : *REQ0000650*

Kindly furnish this office with a written quotation for supply of goods/ services as detailed below. The quotation must be submitted on the letterhead of your Business and Brought to our offices 3 Nyala Street, Phalaborwa not later than **04/04/2022 at 12H00**

QUANTITY	Description	PRICE/UNIT (Inc. VAT)	DELIVERY PERIOD
1	Installation of Clear Vu fence as per attached specification		
1	Erection of Carport as per attached specification		

**Please number your quotes (Your Ref no)**

The following conditions will apply:

- > Price (s) quoted must be valid for at least thirty (30) days from date of your offer.
- > The municipality retains the prerogative to reject any quotes it deems to be excessive
- > A firm delivery period must be indicated.
- > Tax Clearance Certificate
- > A service provider be registered with central supplier database (CSD)
- > Registered with CIPRO (CK 1 or 2 document)
- > BBBEE Certificate certified by a SANAS accredited institution.
- > Completed MBD4 (Declaration of Interest) Form
- > Completed MBD6.2 FORM
- > Minimum Local content threshold: 100%

**Fill in and Return the Declaration of Interest Form.**

**INSTALLATION OF CLEAR VU FENCING AT WHITE HOUSE & ERECTION OF CARPORT**

ITEM	DESCRIPTION	UNIT	QTY	RATE	AMOUNT
1	<b>PRELIMINARIES &amp; GENERAL</b>				
	a)Site establishment, i.e allowance for arrangement of site logistics, collection of materials and other	Item	1		
2	<b>SITE CLEARANCE &amp; EXCAVATIONS</b>				
	a)Remove trees along the perimeter of fence, also conduct site visit together with client for exposing of services along the perimeter of the fence	m	112		
	b)Digging of holes/ trenches for Palisade poles, with minimum depth of 400mm but not exceeding 600mm	m3	0.6		
3	<b>INSTALLATION OF PALISADE</b>				
	a)Cast 20Mpa concrete on excavated holes with Poles inside	m3	0.6		
	b)Install 3.3m x 2.4m Clear Vu Panels	m	112		
	c) Install Pole	No	34		
4	<b>GATE</b>				
	Design, 6m construct double steel with clear vu panels and also sliding rail imbedded in concrete	each	1		
5	<b>CARPORT</b>				
	Construction of Carport to cater for six vehicles ( 12m x 6m) , with IBR roof sheets on top of steel lipped channels and Purlins, Design to be similar with Flea Market carport	each	1		

Total                     

