



BA-PHALABORWA MUNICIPALITY  
MEMORANDUM  
- BUDGET AND TREASURY -

TO : Prospective Service Provider  
FROM : SCM /STORES  
DATE : 18/08/2021  
ENQUIRIES : STORES  
TELEPHONE : 015 780 6346/61162  
REF : 135773

Kindly furnish this office with a written quotation for supply of goods/ services as detailed below. The quotation must be submitted on the letterhead of your Business and Brought to our offices 3 Nyala Street, Phalaborwa not later than 26/08/2021 at 12H00

| QUANTITY | Description   | PRICE/UNIT<br>(Inc. VAT) | DELIVERY<br>PERIOD |
|----------|---|--------------------------|--------------------|
| 7        | Construction of 10KL Jojo tank platform               |                          |                    |
|          | ➤ Supply Materials and built as per attached spec and |                          |                    |
|          | Drawing   |                          |                    |
|          |   |                          |                    |
|          |   |                          |                    |
|          |   |                          |                    |
|          |   |                          |                    |

**Please number your quotes (Your Ref no)**


The following conditions will apply:

- Price (s) quoted must be valid for at least thirty (30) days from date of your offer. ➤ The municipality retains the prerogative to reject any quotes it deems to be excessive ➤ A firm delivery period must be indicated.
- Tax Clearance Certificate
- A service provider be registered with central supplier database (CSD)
- Registered with CIPRO (CK 1 or 2 document)
- BBBEE Certificate certified by a SANAS accredited institution.
- Completed MBD4 (Declaration of Interest) Form
- Completed MBD6.2 FORM


Fill in and Return the Declaration of Interest Form.

**BOQ FOR CONSTRUCTION OF 10KL JOJO TANK PLATFORM**

| ITEM | DESCRIPTION  | UNIT | QTY   | RATE | AMOUNT |
|------|--|------|-------|------|--------|
| 1    | <b>PRELIMINARIES &amp; GENERAL</b>   |      |       |      |        |
|      | a) Allowance for site establishment  | Item | 1     |      |        |
|      | <b>SITE CLEARANCE, EXCAVATIONS, CONC AND BRICKWORK</b>   |      |       |      |        |
| 2    | Clear site and remove all veges, shrubs etc  | m2   | 6,25  |      |        |
| 3    | Excavations to trenches of foundations n.e 0.5m deep and 600mm width   | m2   | 1,656 |      |        |
| 4    | Cast concrete to strip footing of 600mm x 150mm with 19mm concrete/20Mpa   | m3   | 0,83  |      |        |
| 5    | Counstruction of 220mm width brickwall, bricks to have a minimum compressive strength of 10MPa   | m2   | 6     |      |        |
| 6    | Fill material under foundations and floors to be as follows:<br>G6 Material or better PI < 6<br>Compacted to 95% MOD AASHTO in layers of 150mm<br>Non-cohesive and free draining | m3   | 1,56  |      |        |
| 7    | 200mm Thick concrete slab with REF 395 Mesh  | m3   | 0,86  |      |        |
| 8    | 4mm Galvanised wire cast into concrete slab  | no   | 4     |      |        |



Total




10kl PVC TANK ON MASONRY STAND

| REV # | DATE | CHK | APP | DESCRIPTION |
|-------|------|-----|-----|-------------|
|       |      |     |     |             |
|       |      |     |     |             |
|       |      |     |     |             |
|       |      |     |     |             |

CLIENT


MUTEO CONSULTING

**MUTEO**  
CONSULTING



PLAN VIEW

- 1. GENERAL NOTES**
- 1.1. All work to be done in accordance with the National Building Regulations and the relevant SABS Specifications.
  - 1.2. All drawings to be read in conjunction with supplier drawings and any discrepancies must be reported to the Engineer prior to any setting out of work.
  - 1.3. No structural alterations are to be made without amended drawings.
  - 1.4. All drawings must be checked by the Contractor and any discrepancies should be reported to the Engineer before any work commences.
  - 1.5. Contractor to ensure that stability of banks and excavations are continuously maintained throughout the construction period.
- 2. CONCRETE WORKS**
- 2.1. No concrete is to be poured before the Engineer has inspected and approved the fixing of the reinforcement, 48 hours notice is required.
  - 2.2. Breaks in concrete and construction joints are to be made only with Engineer's approval.
  - 2.3. Shuttering and propping may be struck only after the lapse of the following times (in days):  
 Beam sides, walls and unloaded columns: 2  
 Slab soffits without removal of slab props: 4  
 Beam soffits without removal of beam props: 7  
 Props unloaded slabs: 10  
 Props unloaded beams: 14
  - 2.4. Concrete cube strength at 28 days - 20MPa
  - 2.5. All floor levels, unless otherwise indicated, are structural slab levels.
  - 2.7. Special attention to be given to curing of concrete. Exact details to be discussed with Engineer on site prior to pouring of any concrete.
- 3. FOUNDING**
- 3.1. Foundations are subject to alterations as excavations proceed.
  - 3.2. No foundations are to be cast in bases until excavations have been approved by an Engineer.
  - 3.3. All backfill material under foundations and floors to be as follows:  
 G5 Material or better  
 PI < 6  
 Compacted to 95% MOD AASHTO in layers of 150mm  
 Non-cohesive and free draining
- 4. BRICKWORK**
- 4.4. All brickwork to have a minimum compressive strength of 10MPa.
  - 4.5. A construction joint sealed with suitable flexible sealant is to be formed at all junctions between new brickwork and existing brickwork.
- 5. COMPLETION CERTIFICATE**
- 5.1. No completion certificate shall be issued if all material and compaction test results are not submitted to the Engineer.



SECTION A-A

|   |               |            |     |           |                                  |  |
|---|---------------|------------|-----|-----------|----------------------------------|--|
| 59 GROBLER STREET<br>POLOKWANE 0699<br>P.O. BOX 6196<br>POLOKWANE NORTH<br>0750<br>TEL : (015) 291 4065<br>FAX : (015) 291 4043<br>website: www.muteo.co.za | PROJECT APPR. | DATE       | BY  | SIGNATURE | SCALE                            | TITLE<br><b>INSTALLATION OF 10KL WATER<br/>         TANKERS IN LIMPOPO<br/>         TANK PLATFORM SPECIFICATIONS</b><br><br>DRAWING No. LNW/C-S/01 |
|   | DESIGNED      | 02/04/2020 | V.M |           | DO NOT SCALE<br>IF IN DOUBT ASK. |  |
|   | CHECKED       | 02/04/2020 | J.M |           | PROJECT No.<br>LNW 31/19/20      |  |
|   | DRAWN         | 02/04/2020 | V.M |           | DRG SIZE A1                      |  |
|   | PROJECT MNG.  |            |     |           |                                  |  |
|   | APPROVED      |            |     |           |                                  |  |
| CLIENT  |               |            |     |           |                                  |  |