



BA-PHALABORWA MUNICIPALITY
MEMORANDUM
- BUDGET AND TREASURY –

TO : *Prospective Service Provider*
FROM : *SCM /STORES*
DATE : *18/01/2022*
ENQUIRIES : *STORES*
TELEPHONE : *015 780 6362/61*
REF : *REQ310*

Kindly furnish this office with a written quotation for supply of goods/ services as detailed below. The quotation must be submitted on the letterhead of your Business and Brought to our offices 3 Nyala Street, Phalaborwa not later than **26/01/2022 12H00**

| QUANTITY | Description | PRICE/UNIT (Inc. VAT) | DELIVERY PERIOD |
|-----------------|---|----------------------------------|----------------------------|
| 1 | REPAIR OF HONEYVILLE STORM WATER CULVERTY BRIDGE | | |
| | ➤ SEE ATTACHED SCOPE OF WORKS | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |

Please number your quotes (Your Ref no)


The following conditions will apply:

- *Price (s) quoted must be valid for at least thirty (30) days from date of your offer.*
- *The municipality retains the prerogative to reject any quotes it deems to be excessive*
A firm delivery period must be indicated.
- *Tax Clearance Certificate*
- *A service provider be registered with central supplier database (CSD)*
- *Registered with CIPRO (CK 1 or 2 document)*
- *BBBEE Certificate certified by a SANAS accredited institution.*
- *Completed MBD4 (Declaration of Interest) Form*
- *COMPLETE MBD6.2*

HONEYVILLE CULVERT BRIDGE

| ITEM NO | DESCRIPTION | UNIT | QUANTITY | RATE | AMOUNT |
|---------------------------------------|---|------|----------|------|--------|
| 12.00 | 1200: GENERAL REQUIREMENTS AND PROVISIONS | Sum | | | |
| B12.02 | Services | | | | |
| | (a) Traffic Accommodation | | | | |
| TOTAL SECTION 1200 CARRIED TO SUMMARY | | | | | |

| ITEM NO | DESCRIPTION | UNIT | QUANTITY | RATE | AMOUNT |
|---------------------------------------|---|--------------------------|----------|------|--------|
| 13.00 | 1300: CONTRACTORS ESTABLISHMENT ON SITE | Lump Sum | | | |
| B13.01 | <p>AND GENERAL Q8_OBLIGATIONS</p> <p>The Contractors genera' obligations:</p> <p>(a) Fixed obligations 4</p> <p>(b) Value-related obtigations</p> <p>(c) Time-related ob'igations</p> | Lump Sum month | | | |
| TOTAL SECTION 1300 CARRIED TO SUMMARY | | | | | |



| ITEM NO | DESCRIPTION | UNIT | QUANTITY | RATE | AMOUNT |
|---------------------------------------|------------------------------------|------|----------|------|--------|
| 17.00 | <u>1700: CLEARING AND GRUBBING</u> | | | | |
| 17.01 | (a) Clearing and grubbing | | | | |
| | (i) Within the road reserve | ha | 0.03 | | |
| TOTAL SECTION 1700 CARRIED TO SUMMARY | | | | | |

SCHEDULE O: SECTION 2200 HONEYVILLE CULVERT BRIDGE

| ITEM | DESCRIPTION | UNIT | QUANTITY | RATE | AMOUNT |
|-----------------------|---|----------------|----------|------|-----------|
| 22.00 | 2200: PREFABRICATED CULVERTS | m ³ | | | |
| 822.01 | Excavation: (a) Excavating soft material situated the following depth ranges below the surface | | | | |
| | 4 | | | | |
| | (i) 0m up to 1.15m | | | | |
| | (ii) Exceeding 1.5m up to 3.0m | | | | |
| 22.02 | Backfilling: | | 50 | | |
| | (a) using the excavated material | | 5 | | |
| | (b) Using imported selected material compacted to MOD AASHTO | | 15 | | Rate only |
| 22.03 | (c) Extra over subitems 22.02(a) and 22.02(b) for soil cement backfilling (3% cement) | | | | Rate Only |
| | Concrete pipe culverts: | NO | | | |
| | (b) On Class B bedding: | | | | Rate Only |
| 22.05 | (i) dia (Class 1000) | | | | |
| | (ii) SCOMM diar (Class 1000) | | | | |
| | Portals and Rectangular Culverts: | | | | |
| 22.07 | (i) 1200 x 900 (Labour only). The Municipality to supply with Portable culverts | | 21 | | |
| | Cast In situ concrete and formwork: | | | | |
| | (b) In floor slabs for portal or rectangular culverts including formwork, joints and Class O2 finish for: | | | | |
| | (i) Class 25/19 concrete | | 37 | | |
| TOTAL CARRIED FORWARD | | | | | |

| ITEM | DESCRIPTION | UNIT | QUANTITY | RATE | AMOUNT |
|-------|---|------|----------|------|-----------|
| | AMOUNT BROUGHT FORWARD | | | | |
| | | kg | 9 | | |
| | (d) Formwork of concrete under subitem 22.07(c) | kg | | | Rate Only |
| | (i) Vertical formwork for F 1 surface finish | | | | |
| 22,08 | Concrete backfill for Culverts | | 250 | | |
| 22,10 | (a) 25 mpa concrete for backfilling | | 55 | | |
| | Steel reinforcement: | | | | |
| | (c) High tensile steel mesh: | | | | Rate Only |
| | (i) Ref. 245 | | | | |
| 22,18 | (iii) Ref. 395 | | | | |
| | Brickwork | | | | |
| | (i) Headwall and Wing wail | | | | |
| | TOTAL SECTION 2200 CARR'ED TO SUMMARY | | | | |

| ITEM NO | DESCRIPTION | | QUANTITY | RATE | AMOUNT |
|---------------------------------------|---|--|--------------|------|--------|
| | 5100: PITCHING STONEMASONRY ETC. Stone pitching: (a) Grouted stone pitching (b) Gabions (2mx1m) | | 55 55 | | |
| TOTAL SECTION 5100 CARRIED TO SUMMARY | | | | | |

SCHEDULE E:
HONEYVILLE CULVERT BRIDGE

SECTION 5600

| ITEM NO | DESCRIPTION | UNIT | QUANTITY | RATE | AMOUNT |
|---------------------------------------|---|------|----------|------|--------|
| 56.00 | 56002 ROAD SIGNS | No | 4 | | |
| 856.10 | Danger Plates (a) Type W4011W402 back-to-back at culverts (1200mm height) | | | | |
| TOTAL SECT'ON 5600 CARRIED TO SUMMARY | | | | | |

SCHEDULE G:
HONEYVILLE CULVERT BRIDGE

SECTION 8100

| ITEM NO | DESCRIPTION | UNIT | QUANTITY | RATE | AMOUNT |
|---------------------------------------|---|----------|----------|-------|------------|
| 81.00 | <u>8100: TESTING MATERIALS AND WORKMANSHIP</u> | Prov sum | 8 000 | 10.0% | R 8 000,00 |
| 881.02 | Other special tests requested by the Client | | | | R 800,00 |
| | (a) Other special tests requested by the client | | | | |
| | 4 | | | | |
| | (b) Handling cost and profit in respect of sub-item 881_02(a) | | | | |
| TOTAL SECTION 8100 CARRIED TO SUMMARY | | | | | R 8 800,00 |



HONEYVILLE CULVERT BRIDGE C2.3 SUMMARY OF BILL OF QUANTITIES

SCHEDULE A : ROADWORKS

| SECTION | DESCRIPTION | AMOUNT TENDERED |
|---------|---|-----------------|
| 1200 | General requirements and provisions | |
| 1300 | Contractors establishment on site and general obligations | |
| 1700 | Clearing and grubbing | |
| 2200 | Prefabricated Culvert Structure | |
| 5100 | Pitching, stonework. etc. | |
| 5600 | Road Signs | |
| 8100 | Testing materials and workmanship | 8 800,00 |
| | TOTAL SCHEDULE A | |

32.4 CALCULATION OF TENDER SUM

| | |
|-------------------------------|--|
| TOTAL SCHEDULE A : ROADWORKS- | |
| TENDER (CONTRACT) SUM | |
| SUBTOTAL | |
| ADD : VAT | |

| | |
|--|--|
| TENDER (CONTRACT) PRICE CARRIED TO FORM OF ACCEPTANCE (Page C.3) | |
|--|--|

Note : Tender sum is the value of the offered total of the prices exclusive of VAT, contingencies, CPA and special materials but including contractual variations.