



BA-PHALABORWA MUNICIPALITY
MEMORANDUM
- BUDGET AND TREASURY -

To : Prospective service provider
From : SCM/stores
Date : 04/09/2023
Enquiries : Procurement Office
Telephone : 015 780 6361/62
Ref : REQ3592

Kindly furnish this office with a written quotation for supply of goods/ services as detailed below. The quotation must be submitted on the letterhead of your Business and Brought to our offices No.3 Nyala Street, Phalaborwa not later than 12/09/2023 at 12H00

QUANTITY	Description	Price/unit (Inc. Vat)	Delivery Period
01	Refurbishment of at Letaba Beer garden as per attached specification,		
	NB: Warranty of works required for a year period and NHBRC certificate for compliance		

Please number your quotes (Your Ref no)

The following conditions will apply:

- Price (s) quoted must be valid for at least thirty (30) days from date of your offer.
- The municipality retains the prerogative to reject any quotes it deems to be excessive
- A firm delivery period must be indicated.
- Tax Clearance Pin
- A service provider be registered with central supplier database (CSD)
- Completed MBD4 (Declaration of Interest) Form
- Evaluation criteria: 80/20 (Whereby 80 is for price and 20 is for Objective goals)
20 is further evaluated: 20 for 100% Black owned;
18 for +51% Black owned; and
14 for Less than 51% Black owned



DEPARTMENT : TECHNICAL SERVICES

DATE : 10/08/2023

RE: BOQ AND SCOPE OF WORK AT BEER GARDEN

Item no	Description	unit	Qty	rate	amount
1	Demolitions				
1.1	Remove old IBR roof sheets together with roof ties and bracings and barge boards	m ²	104		
1.2	Remove the entire ceiling inside the building	m ²	104		
1.3	Remove damaged IBR roof sheets on height exceed 2m high but n.e 4m high	m ²	175,74		
2	Roofing				
2.1	Erect new timber trusses and purlings with max spacing of 800 c/c and branderings	m ²	104		
2.2	Install new IBR roof sheets with min of 0.5mm thickness SABS approved	m ²	94		
2.3	Install new IBR roof sheets on height exceed 2m high but n.e 4m high	m ²	175,74		
2.4	Install new 155mm barge boards	m	123,7		
2.5	Installation of New ceiling on 38 x 38mm branderings	m ²	104		
2.6	Remove and Install new gutters and downpipes	item	1		
3	Painting				
3.1	Spray Paint the entire roof with paint Traffic green roof paint two coats	m ²	279,74		
3.2	Painting of Barge boards and Carbolium to trusses on overhang and eaves	item	1		

Total

=====
=====