



**TO** : *Prospective Service Provider*  
**FROM** : *SCM /STORES*  
**DATE** : *25/03/2022*  
**ENQUIRIES** : *STORES*  
**TELEPHONE** : *015 780 6361/62*  
**REF** : *REQ0000649*

Kindly furnish this office with a written quotation for supply of goods/ services as detailed below. The quotation must be submitted on the letterhead of your Business and Brought to our offices 3 Nyala Street, Phalaborwa not later than **04/04/2022 at 12H00**

<b>QUANTITY</b>	<b>Description</b>	<b>PRICE/UNIT (Inc. VAT)</b>	<b>DELIVERY PERIOD</b>
1	Removal of Asbestos roof sheets and installation of IBR galvanised		
	Roof sheeting as per attached specification		

**Please number your quotes (Your Ref no)**

The following conditions will apply:

- > Price (s) quoted must be valid for at least thirty (30) days from date of your offer.
- > The municipality retains the prerogative to reject any quotes it deems to be excessive
- > A firm delivery period must be indicated.
- > Tax Clearance Certificate
- > A service provider be registered with central supplier database (CSD)
- > Registered with CIPRO (CK 1 or 2 document)
- > BBBEE Certificate certified by a SANAS accredited institution.
- > Completed MBD4 (Declaration of Interest) Form
- > Completed MBD6.2 FORM
- > Minimum Local content threshold: 100%

**Fill in and Return the Declaration of Interest Form.**



DEPARTMENT : TECHNICAL SERVICES

DATE : 07/ 03/ 2022

**RE: BOQ AND SCOPE OF WORK AT PARKS OFFICES**

Item no	Description	unit	Qty	rate	amount
<b>1</b>	<b>Demolitions</b>				
1.1	Remove old Asbestos roof sheets together with roof ties and bracings	m <sup>2</sup>	94		
1.2	Remove the entire ceiling inside the building	m <sup>2</sup>	94		
<b>2</b>	<b>Roofing</b>				
2.1	Erect new steel purlins/timber purlings with max spacing of 800 c/c and branderings	m <sup>2</sup>	94		
2.2	Install new IBR roof sheets with min of 0.5mm thickness SABS approved	m <sup>2</sup>	94		
<b>3</b>	<b>Masonry</b>				
3.1	Seal the entire beamfilling with 220mm thick brickwork on all sides including internal walls	m <sup>2</sup>	18		
<b>4</b>	<b>Ceilings</b>				
4.1	Install Rhinoboard ceiling on 38 x 38mm branderings	m <sup>2</sup>	86		
4.2	Install 75mm nutec cornice	m	72		