



BA-PHALABORWA MUNICIPALITY
- BUDGET AND TREASURY –
- PROCUREMENT AND STORES -

TO : Prospective Service Provider
FROM : SCM/STORES
DATE : 12/12/2016
ENQUIRIES : STORES
TELEPHONE : 015 780 6362/61
REF : 127903

Kindly furnish this office with a written quotation for supply of goods/ services as detailed below. The quotation must be submitted on the letterhead of your Business and Brought to our offices No 03 Nyala Street Phalaborwa 1390 not later than 22/12/2016 at 12H00.

QUANTITY	Description	PRICE/UNIT (Inc .VAT)	DELIVERY PERIOD
01	<i>Repairs of 650m 11kv overhead line from Selati Substation to Mainsubstation.</i>		
	See Full specifications below		

Please number your quotes (Your Ref no)

The following conditions will apply:

- Price (s) quoted must be valid for **at least thirty (30) days** from date of your offer.
- The municipality retains the prerogative to reject any quotes it deems to be excessive
- A firm delivery period must be indicated.
- Original Tax Clearance Certificate
- A service provider be registered with Ba-Phalaborwa database
- Registered with CIPRO (CK 1 or 2 document)
- BBBEE Certificate certified by a SANAS accredited institution.
- Fill in and Return the Declaration of Interest Form.
- CSD registration summary report

The municipality reserve a right not to appoint on the advertised



BA-PHALABORWA MUNICIPALITY
- BUDGET AND TREASURY –
- PROCUREMENT AND STORES -

Emergency Repair of portion of 11kV line damaged by Storms

Short Specification.

Scope of works.

The scope of works covers the construction of approximately 650m of a new 11kV overhead line to replace a damaged part of one of the Selati to Main Substation feeders. The existing "Panther" conductor must be re-used.

There are 2 H-pole Structures (strain) and 7 single pole structures (suspension) with stand-off insulators. Span lengths are 100m maximum, and contractors will ensure that all material is quoted for, whether included in the Bill of Quantities or not.

All material will comply to the relevant SABS/SANS specifications, and proof of such will be made available on request.

Insulators will be suitable for use with "Panther" conductor at 100m span lengths.



BA-PHALABORWA MUNICIPALITY
- BUDGET AND TREASURY -
- PROCUREMENT AND STORES -

Item	Description	unit	qty	Supply and delivery to site		Installation	
				Rate	Total	Rate	total
1	Wooden poles, 11m length, 220mm minimum top diameter, planted to 1,8m depth	each	9				
2	Cross arms, 3,5m, 160 minimum mm top diameter, complete with cross braces	each	4				
3	Tension Insulators, 22kV	each	15				
4	Post Insulators 22kV 10kN	each	15				
5	Stays, complete with baseplate, stay insulator, thimble, etc.	each	8				
6	Holes (excavation) for poles	each	9				
7	Holes (excavation) for stays.	each	8				
8	Removal of existing conductor (Panther) from existing structures and installing it on new structures, tensioning it according to applicable tables	m	2100				
9	Removing all old material and rubble from site, rehabilitation of site	item	1				
10	Provision of Safety File to satisfaction of the client, and ensuring all regulations and requirements regarding safety is adhered to.	item	1				



BA-PHALABORWA MUNICIPALITY
- BUDGET AND TREASURY -
- PROCUREMENT AND STORES -

11	Any other items regarded necessary for the successful completion of the project, including all bolts, nuts, U-bolts, washers, twin ties, etc. Contractors are required to visit the site to ensure they provide a complete quotation, no claims in this regard will be entertained.	sum	1				
12	Sub Totals					=	+
13	Total Amount					=	=
14	VAT @ 14%						=
15	Grand Total						=

Time for completion from date of Order _____ weeks

Name of Contractor _____

Signature _____

Date _____