



BA-PHALABORWA MUNICIPALITY

- BUDGET AND TREASURY –

- PROCUREMENT AND STORES -

TO : Prospective Service Provider
FROM : SCM/STORES
DATE : 14/11/2017
ENQUIRIES : STORES
TELEPHONE : 015 780 6362/61
REF : 129010

Kindly furnish this office with a written quotation for supply of goods/ services as detailed below. The quotation must be submitted on the letterhead of your Business and Brought to our offices No 03 Nyala street, Phalaborwa 1390 not later than 23/11/2017 at 12H00.

QUANTITY	Description	PRICE/UNIT (Inc .VAT)	DELIVERY PERIOD
01	Renovation of flea market Building <i>See attached full specification below</i>		

Please number your quotes (Your Ref no)

The following conditions will apply:

- Price (s) quoted must be valid for **at least thirty (30) days** from date of your offer.
- The municipality retains the prerogative to reject any quotes it deems to be excessive
- A firm delivery period must be indicated.
- Original Tax Clearance Certificate
- Registered with CIPRO (CK 1 or 2 document)
- Fill in and Return the Declaration of Interest Form.
- CSD registration summary report (print out)
- BBBEE Certificate certified by SANAS accredited Institution or certified sworn affidavit

Disclaimer: Goods of inferior quality will not be accepted. SABS approved materials required.



BA-PHALABORWA MUNICIPALITY

- BUDGET AND TREASURY -

- PROCUREMENT AND STORES -



DEPARTMENT : TECHNICAL SERVICES

DATE : 01/ 11/ 2017

RE: BOQ AND SCOPE OF WORK AT BURNT FLEA MARKET BUILDING

Item no	Description	unit	Qty	rate	amount
1	Demolitions				
1.1	Demolish Trapezium wall and triangular wall above ceiling level, with a height exceeding 3m high but N.e 5m high	m ²	87		
1.2	Prepare flaky burnt plastered area for plaster	m ²	199		
2	Masonry				
2.1	Demolish 3 courses of burnt face bricks and rebuild with class II mortar	m ²	54		
3	Paintings				
3.1	Paint Walls with 3-in-1 sealer/primer/undercoat	m ²	199		
3.2	Apply final coat on walls	m ²	199		
4	Ceilings				
4.1	Install Rhinoboard ceiling on 38 x 38mm branderings	m ²	96		
4.2	Install 75mm nutec cornice	m	96		
5	Ironmongery & carpentry				
5.1	Install Meranti FLB open braced doors and locks	no	15		
6	Roofings				
6.1	Install 114mm x 38mm Tie beam at 800 c/c for 50 x 76mm purlins on the parapet roof and lay concrete roof tiles	m ²	114		
6.2	Install YBR Roof sheets, with tie beams and Purlin	m ²	64,5		
7	Tiling				
7.1	Remove old tiles and Install new ceramic tiles on floors	m ²	48		
8	Glazing				
8.1	Install 3mm float glasses at NE4 openings and fixtures	no	6		

523620
733
124