

- Construction of layer works – roadbed, selected ,sub-base and base
- Stabilization of base layer
- Surfacing with 80mm interlocking block pavement
- Installation of culverts
- Construction of concrete v-drains and edge beams
- Construction of Sub-Soil drainage
- Installation of kerbs
- Installation of guardrails
- Construction of speed humps 10
- Stone pitching and gabion installation
- Installation of road signs
- Road markings

### C3.1.4 Location of the Works

The proposed project is located in the Namakgale Block E  $\pm$  12km outside of Phalaborwa Town through R530 Road within Ba-Phalaborwa Municipality.

The coordinate positions of the settlement are: 23°57'51.44"S 31° 03'30.48"E.

### C3.1.4 Construction Program and Project Duration

It is specifically brought to the notice of the Contractor that time is critical on this project, and the construction period will be a major factor in the award of the tender.

Tenderers shall submit with their tender their **preliminary weekly programme for the construction** of the Works under this contract to suit their proposed method of executing the Works. The programme shall be sufficiently detailed to differentiate between the various activities so that the contract may be properly evaluated.

The duration of this project is (12) Twelve months.

### C3.1.5 Change in works

The Engineer may, from time to time by order in writing without in any way vitiating the Contract or giving to the Contractor any claim for additional payment, require the Contractor to proceed with the execution of the works in such order as in his opinion may be necessary, and may alter the order of or suspend any part of the Works at such time and times as he may deem desirable and the Contractor shall not, after receiving such written order, proceed with work ordered to be suspended until he shall receive a written order to do so from the Engineer. Where the work must of necessity be carried out in conjunction with work of other Contractors, or with that of the Employer, it shall be co-ordinated and arranged in such a manner as to interfere as little as possible with the progress of such other work so as to