

C3.1 DESCRIPTION OF WORKS

The description of the project contained in this section is merely an outline of the contract works and does not limit the work to be carried out by the Contractor under this contract. The extent and scope of the work to be carried out as part of the contract can change, due to changes to the priority of certain portions of the work, as determined by the client, changes to budgetary constraints or emergency works that have to be completed.

C3.1.1 Employer's Objectives

The employer's objective is to deliver public infrastructure in a sustainable and environmentally friendly manner, in close consultation with the community. In this project, labour intensive construction methods will be used.

C3.1.2 Overview and Location of Works

The Works to be carried out is as described on the drawings (Part C5.3: Contract Drawings) and summarized below:

This project comprises the **UPGRADING OF AUBREY CARWASH TO KANANA FROM GRAVEL TO PAVED CONCRETE INTERLOCKING BRICKS**

C3.1.3 Extent of Works

The project network consists of the listed streets section

Project Name	Street No./Description	Total Length
Upgrading of Aubrey Carwash to Kanana from Gravel to Paved Concrete Interlocking Bricks Road	New Proposed road inclusive of belmouth	2.6(km)
	TOTAL	+/-2.6km

The total length of roads to be constructed is ± 2.6 km. The streets will be upgraded from gravel to surfacing with 80mm Interlocking Concrete Block Pave. The major activities for the project will include, among other, the following;

- Clearing and grubbing
- Relocation of services (Eskom and water)
- Removal of indigenous trees
- Moving back fences of encroaching stands
- Mass earthwork
- Hard rock blasting